





Watershed Advisory Committee Cuyahoga River - North October 2018

REGIONAL SEWER DISTRICT

REGIONAL

STORMWATER

MANAGEMENT

PROGRAM





Agenda

- Sewer District Updates
 - Community Cost-Share
 - Local Sewer System Evaluation Studies
- Stormwater Master Plan
- Stormwater Inspection and Maintenance
 - Urgent Response Process
 - Problems to Projects
 - Community Meetings on Crossings and Culverts
- Stormwater Construction Plan
 - 2018 Project Updates
 - 2019 Annual SW Construction Plan Review
 - Construction Project Oversight





Community Cost-Share: 2018

• CCS Funds Balance (8/31/2018)

\$ 22,039,931

67 projects w/ executed agreement

\$ 9,150,615

17 approved allocation agreements

\$ 7,539,502

• CCS Funds available to Member Comm.

\$ 5,349,814

30 of 55 Member Communities currently participating





Community Cost-Share Project Ideas

Examples of the Community Cost-Share Progam





The Community Cost-Share Program provides funding to Member
Communities for Community-specific stormwater management

3 4 5 6 7 8 9 10 11 12 13 14 15 16

projects. To implement the Community Cost-Share Program, the Northeast Ohio Regional District (District) has formed a financial account termed "Community Cost-Share Account" for the aggregation and dissemination of funds derived from Stormwater Fee collected in each Member Community.

25% of the total annual Stormwater Fee collected in each Member Community is allocated to the Community Cost-Share Account for each Member Community. The Community Cost-Share Account is under the control of the District, with disbursement of funds to Member Communities through a grant application and reimbursement process. To access Community Cost-Share Program funds, Member Communities must maintain

compliance with Title V: Stormwater Management Code. A Community Cost-Share Program Project must clearly promote or implement the goals and objectives of the District set forth in Title V and must be intended to address current or minimize new, stormwater flooding, erosion, and water quality problems.

More Information

WTL_Communities

Beachwood

Bedford

Bedford Heights

Berea

Bratenahl

Brecksville

Broadview Heights


Brook Park

Brooklyn

Brooklyn Heights

Cleveland


Cleveland Heights








Local Sewer System Evaluation Studies






Stormwater Master Plan




Study Process







Stormwater Master Planning (status through 9/30)




Stormwater Master Plan Study Area


Total Study Area

- > 99,000 acres (all within SWSA)
- > 11 Subwatersheds in the SWSA
- > 23 WAC Member Communities

Budget: \$8.02 Million









Stormwater Master Plan Field Work Project Status



Task Item Status – 100% Complete

- Survey work
- Culverted Stream Inspection (25 miles)
- Open Channel Streams
- Crossings
- Major Structures
- Basins (15 total)
- High Water Mark Monitoring






Stormwater Master Plan

Modeling & Problem Identification Project Status

Task Item Status: 55% Complete

- Stickney Creek Model & Problem ID Complete
- B.C. Main Branch Model & Problem ID Complete
- B. C. West Branch Model & Problem ID Complete
- West Creek Model Complete Problem ID Begin
- Hemlock Model Complete
- Small Tributaries In Progress
- Mill Creek In Progress
- RSS Terminus Changes: 12 approved Additional 4.3 miles







Stormwater Master Plan

Alternative Evaluation Project Status

Task Item Status: 32% Complete

- Stickney Creek Complete
- B.C. Main Branch Alternatives Review Complete
- B. C. West Branch Alternatives for Brook Park & Cleveland Area
- Basin Evaluations In Progress







Sam's Club – Brooklyn, Ohio – Big Creek Subwatershed

Problem:

- Stormwater inundation and impacts to Sam's Club, Brookpark Road & surrounding areas including fueling station
- Brookpark Road overtops around a 1-yr. storm
- Sam's Club parking lot begins to flood between the 2- and 5- yr storms
- Water enters the Sam's Club Building around the 10-yr storm








Problem Overview

- Total Drainage Area 8781 acres
- Percent Impervious 38% acres
- Problem Area Specific Target volume to manage for 100-year LOS 1,800 acre-feet or ≈1,361 football fields
- Watershed-wide: Target volume to manage for 100-yr LOS 3,300 acrefeet or 2,496 football fields
- Sam's Club building & parcel site within both the 100-year FEMA & CRN SWMP model floodplains






No upstream development at all

- All impervious area (development) removed
- Review 100-yr design storm (CRN SWMP parameter)
- Review depth at Sam's Club entrance 767.3

Results

 Inundation depth 1 ft above Sam's Club entrance elevation








Use open land areas –regardless of current ownership

- Review 100-yr design storm (CRN SWMP parameter)
- Review depth at Sam's Club entrance 767.3

Results


- Potential open area is about 440 acres
- Needed storage of 1,500 acre-ft exceeds potential
- Current watershed does not have enough open areas to address levels of flooding
- Available open areas at Walmart locations for storage opportunities can not remedy issues



@neorsc



Stormwater Master Plan Level of Service Evaluation – Mitigation Options



<2-year Scenarios

- Current conditions (Do Nothing)
- Raise Brookpark Road
- Channel re-alignment south of Brookpark Rd
- Sam's Club/Walmart bridge removal

<5-year Scenario (New)

CSX crossing modification

<10-year Scenario</p>

Channel widening into Walmart parking lot

<25-year Scenario (New)</p>

Channel widening into Walmart parking, CSX crossing upsizing & width increase at Brookpark Rd

Results:

- Increased floodplain storage from <2-yr to <25-yr LOS (up to <10-yr with channel widening only)
- Inundation depths reduced by about 1 inch at 100-yr
- Downstream problem areas show increase inundation depths



Stormwater Master Plan

Community Communication


- Member Community Work Plans
- Meet with communities
 - Problem Area Review
- Recommendations and Community Report

Your Watershed Team Leader serves as the point of contact between the communities and the District






Questions



Stormwater Inspection and Maintenance (SWIM)



SWIM Agenda

- Introduce SWIM Team Members
- Urgent Storm Event Response Process
- Small Scale Maintenance Projects
- Upcoming Community Meetings on Crossings





Westside SWIM Team

- Mark Link
 Supervisor
- Christina Silea
 Inspector
- Nikki Velez
 Inspector
- Claire Posius

 Project Coordinator
- Martina Jozanovic

 Data Maintenance

 Administrator

Eastside SWIM Team

- Keith McClintock
 Supervisor
- Jon Brauer
 Inspector
- Anne Roberto
 Inspector
- Mark Hornyak
 Project Coordinator
- Eric Baker

 Data Maintenance

 Administrator





SWIM Agenda

- Introduce SWIM Team Members
- Urgent Storm Event Response Process
- Small Scale Maintenance Projects
- Upcoming Community Meetings on Crossings





SWIM Progress Status

Urgent Storm Response Case Study April 15, 2018 Storm Event





SWIM Urgent Storm Event Response Process

- Review Advanced Warning Notifications
 - e.g., National Weather Service
- Field Check and Clean Known Problem Assets Prior to Storm
- Track Rainfall for Size of Storm (e.g., 10-yr, 24-hr) &
 Monitor Live Field Data for Evidence of Flooding
- Analyze Media, Customer & Member Community reported flooding





SWIM Urgent Storm Event Response Process

- Immediately Field Inspect Problem Assets Upon Receded Flooding
- Mobilize Contractors for Post-Storm Event Response Maintenance






Urgent Storm Event Response Case Study

April 15-16, 2018





Review of Advanced Warning Notifications




4/15/18 NWS
Notifications
received at
5:02 PM
(Sunday)
immediately
prior to the
storm





Sites SWIM Routinely Checks for Debris and Prior to Large Storms with Advanced Warning

SWIM routinely visits 21 sites for debris maintenance












Immediately Field Inspected Problem Assets Upon Receded Flooding



SWIM has a list of 42 known sites that are prone to flooding


Field inspected when reported heavy rainfall, high streams, or media reports of flooding in the area

Additional sites are added per media reports or field observations





Mobilized Contractors to Perform Post-Storm Response Maintenance



79 site inspections

18 debris removal projects (many the same day as inspection)

Average yardage of debris was low compared to previous removals due to preventative maintenance





Rocky River: Rocky River East Branch

Member Community: North Royalton

Asset ID: RY00434


Maintenance Project: Debris Removal (10 CY)







Using Trail Cameras to Support the RSMP





















SWIM Agenda

- Introduce SWIM Team Members
- Urgent Storm Event Response Process
- Small Scale Maintenance Projects
- Upcoming Community Meetings on Crossings





Small Scale Maintenance Projects



21 small scale maintenance projects are underway as a pilot preventative maintenance program

- 11 Structural
 Maintenance projects
- 10 Streambank
 Stabilization projects






Small Scale Maint Project: Streambank Stabilization Cuyahoga River: Hemlock Creek



Small Scale Maint Project: Streambank Stabilization Cuyahoga River: Hemlock Creek



- Remove Failing Gabions
- Lay banks to a stable slope
- Install live branch layering and rock toe protection





SWIM Agenda

- Introduce SWIM Team Members
- Urgent Storm Event Response Process
- Small Scale Maintenance Projects
- Upcoming Community Meetings on Crossings





Upcoming Community Meetings to Discuss State of RSS Crossings

District Stormwater Service Area

2018 SWSA Structural Integrity Report Card	SWSA Subwatersheds				
Α	12				
В	38				
С	5				
D	1				
F	0				
Total	56				

The District continues to inspect RSS assets (55%)

Almost all RSS crossings have been inspected

Meetings will review SWIM findings and next steps for implementation and financing

- 327 SWSA RSS assets with Condition Rating = 4 or 5
- 63 SWSA RSS Crossing assets Condition Rating = 4 or 5





Upcoming Community Meetings to Discuss State of RSS Crossings

2018 Cuyahoga River North WAC Structural Integrity Report Card

RSS SUBTOTAL	1,070	451	<u>△</u> 42%	В	Δ	2.26	√	12.00
ASSET CLASS TYPE	RSS COUNT	COND SCORE COUNT	Percent Inspected	Report Card Grade (per structural integrity condition)		Average Structural Integrity Condition		AVG BRE
BASIN	20	15	√ 75%	B+	Δ	1.9	<∕	11.1
CROSSING	325	199	▲ 61%	В	Δ	2.1	Δ	14.9
CULVERTED_STREAM	83	40	▲ 48%	C+	\Pi	2.6	×	20.6
Major Structure	6	1	X 17%	D	×	4.0	×	36.0
STREAM	636	196	3 1%	B-	Δ	2.4	4	7.2

- 101 CRN RSS assets with Condition Rating = 4 or 5
- 13 CRN RSS Crossing assets with Condition Rating = 4 or 5
















Cuyahoga River North Watershed Design



Cuyahoga River North Watershed Design







STICKNEY CREEK RESTORATION & UTILITY REPAIR AT RIDGE ROAD

BROOKLYN, OHIO



SUMMARY

This project will reestablish floodplain storage, slow stream velocities, and create more in-stream and floodplain habitat by restoring up to 1000-feet of urban stream within the City of Brooklyn.

The stream has been eroding toward the Ridge Road Relief Sewer, exposing it and allowing for flow into the sanitary sewer.

This 66-inch sewer will be moved and upsized prior to stream restoration to prevent the inflow of stormwater and to avoid the need to disturb the area in the future.

CUYAHOGA RIVER NORTH

STICKNEY CREEK SUBWATERSHED



Project Details

Asset Number: ST00209

Contract Type: Design/Build

Construction Cost: \$500,000

Estimated Construction NTP:

4th QTR 2018

Watershed Team Leader: FriedmanD@neorsd.org

NORTHEAST OHIO REGIONAL SEWER DISTRICT
















Northeast Ohio Regional Sewer District

Stormwater Design & Construction Program



New Design and Construction Projects Cuyahoga River North

			WAC		Project	Total
	Proposed Project Name	RSS Asset ID(s)	Watershed	Subwatershed	Community	BRE
	West Branch Big Creek Stream Culvert in Brook		Cuyahoga	Big Creek West		
1	Park	WB00167_P1_C01	River North	Branch	Brook Park	72
	Mill Creek_Restoration and Stabilization UPS	MC00115 and	Cuyahoga			
2	Kerruish Basin MC00115 and MC00281	MC00281	River North	Mill Creek	Cleveland	59
	West Creek Streambank and Culvert Stabilization		Cuyahoga			
3	downstream from Ridgewood Road in Parma	WC00196	River North	West Creek	Parma	52
	Big Creek Stream Stabilization Downstream from		Cuyahoga			
4	Ridge Road in Parma	BC00351	River North	Big Creek	Parma	31
			Cuyahoga		Highland	
5	Mill Creek Stream Stabilization in Garfield Heights	MC00057	River North	Mill Creek	Hills	29
	Upper Mill Creek Stabilization and Restoration		Cuyahoga		Highland	
6	Phase II in Highland Hills	MC00135	River North	Mill Creek	Hills	27
	Big Creek_Erosion and Flooding at Local Sanitary		Cuyahoga			
7	Manholes East of Ridge Road	BC00355	River North	Big Creek	Parma	23
	West Creek Tributary Headcut Stabilization in		Cuyahoga		Independen	
8	Independence and Brooklyn Heights	WC00025	River North	West Creek	ce	19
		MC00221,				
	Mill Creek Stream and Floodplain Restoration	MC00136,	Cuyahoga		Highland	
9	Phase 1 in Highland Hills	MC00137, MC00139	River North	Mill Creek	Hills	7





NEORSD Stormwater Design & Construction Program Cuyahoga River North Watershed **ROCKY RIVER** CLEVELAND MC00137 MC00135 MC00133 BROOKLYN MC00281 GARFIELD HEIGHTS WB00167 WB00104 MC00057 BEDFORD HEIGHTS WC00025 BROOK PARK WC00196 PARMA BEDFORD VALLEY VIEW BC00339 INDEPENDENCE MIDDLEBURG HEIGHTS WALTON HILLS BC00355 BC00351 4 Miles **BROADVIEW HEIGHTS** Regional Stormwater System Watershed MACEDONIA CITY District Stormwater Service Area Chagrin River NORTHEAST OHIO REGIONAL SEWER DISTRICT BRECKSVILLE Municipal Boundary Cuyahoga River North REGIONAL **Project Status** Cuyahoga River South STORMWATER Scored Lake Erie Direct Tributaries MANAGEMENT Scheduled **PROGRAM** Rocky River Esri, HERE, Garmin, @ OpenStreetMap

Project Delivery Methods

- GES- Bid-Build
- Design-Bid-Build
- Design-Build
- Small Scale Projects
 - -Under \$50K
 - -\$50K-\$250K






West Creek Bank Stabilization at Parma Care







Multi-Site Streambank Stabilization







Metrics of Success

- 9,336 LF of Stream Restored/Stabilized
- 23,725 Tons of Sediment Removed
- 6.6 Acres of Floodplain Reconnected
- 575 LF of Culverts Repaired/Replaced
- Property Interests Obtained
 - -2 Fee Simple Acquisitions (18 acres)
 - -17 Permanent Easements Acquired






Cuyahoga River North Watershed Construction

6 Active Construction Projects

• 2 in CRN








BIG CREEK STABILIZATION

CLEVELAND, OHIO



SUMMARY

The Big Creek Stabilization project will repair streambanks with riprap and construction of a rock cascade on top of the existing spillway structure to rehabilitate the existing channel.

The current concrete liner will be removed and reused as fill material, and the rock cascade will replace the existing 30-ft drop with a gently sloping cascade to provide energy dissipation.

A low flow channel will be constructed within the rock cascade and a 96-inch outfall will be extended to outlet at the end of the rock cascade. CUYAHOGA RIVER NORTH

BIG CREEK SUBWATERSHED



Project Details

Asset Number:

BC00032

Contract Type:

GES/Bid/Build

Construction Cost:

\$6,505,860

Anticipated Substantial Completion:

4th QTR 2019


Watershed Team Leader: JowettJ@neorsd.org

NORTHEAST OHIO REGIONAL SEWER DISTRICT



COLOMBO PARK STREAM RESTORATION

PARMA HEIGHTS, OHIO



SUMMARY

This project will improve stream function and halt erosion, which is threatening public sanitary sewer infrastructure along Big Creek in Parma Heights adjacent to Colombo Park.

Approximately 400-feet of stream will be realigned, widened, and stabilized to establish new floodplain areas, reduce inchannel velocities and reduce streambank and streambed erosion.

CUYAHOGA RIVER NORTH

BIG CREEK SUBWATERSHED



Project Details

Asset Number: BC00299

Contract Type: GES/Bid/Build

Construction Cost: \$1,544,819

Estimated Construction NTP:

4th QTR 2018

Watershed Team Leader: FriedmanD@neorsd.org

NORTHEAST OHIO REGIONAL SEWER DISTRICT
REGIONAL
STORMWATER
MANAGEMENT
PROGRAM


Beecher's Brook Bank Stabilization







Beecher's Brook Culvert 2002








Beecher's Brook Culvert 2002











CHANNEL EVOLUTION MODEL (SIX STAGES) Simon and Hupp, 1986


Class I. Sinuous, Premodified h<hc




Class II. Channelized* h<hc




Class III. Degradation h<hc




Class IV. Degradation and Widening h>hc



Class V. Aggradation and Widening h>hc




Class VI. Quasi Equilibrium



*Anthropogenic























Beecher's Brook Culvert 2017
































What's Next

- District Stream Restoration Site Visit
 - -October 25 (Thursday) from 2 to 3 pm
 - Meet at 6700 Beta Drive, Mayfield OH,44143
- Annual WAC Representative Designation – January 2019
- Next WAC Meeting March 2019





WTL Contacts

Donna Friedman 216-881-6600 Ext. 6768 friedmand@neorsd.org

Jeff Jowett 216-881-6600 Ext. 6881 jowettj@neorsd.org



Stormwater Program: Community Resources
http://www.neorsd.org/communitystormwaterresources.php



